



Chugach Renewable Generation

Q2 Update of Renewable Energy Plan Activities




Chugach Operations Committee Meeting
July 12, 2023



Presentation Take-Away Messages

1. Two big renewable projects will end study phase in September; if feasible, PPA negotiations in Q4
2. Regulating variable sources is critical
3. Community solar economic evaluation in September
4. Many other projects and policies are in development

Renewable Energy Plan Progression



2020 Goal:

Add 100,000 MWh of renewable generation by March 31, 2025

2021 Renewable Energy Plan

The focus of this update

2023-2027 Strategic Plan Priority 6: Decarbonization

Reduction Goal: at least 35% by 2030
at least 50% by 2040
Using 2012 as baseline, and if no material impact to member rates

Renewable Energy Plan Focus Areas



1. Issue RFP: Issue a Request for Proposal (RFP) for the purchase of renewable energy generation



2. Develop Known Renewable Projects: Continue to pursue potential renewable energy projects



3. Create Policy Changes: Pursue regulation and legislative changes that remove regulatory barriers to the deployment of renewable generation




1. Issue RFP: Issue a Request for Proposal (RFP) for the purchase of renewable energy generation

Focus Area 1


- Issue Request for Proposals
- Goal: Identify renewable projects that can meet or beat Chugach avoided cost. We requested best price, even if higher than avoided cost.

Value and Importance of Multi-Disciplinary Teams

RFP Evaluation Team




Studies Team



Focus Area 1: RFP for Renewable Energy

RFP & Study Process



See Appendix A for additional timeline details.

Focus Area 1: RFP for Renewable Energy

**A dozen proposals received for a wide variety of technologies.
Two proposals under detailed interconnection and integration studies:**

Alaska Renewables
Little Mount Susitna Wind
122 MW
West of Mt. Susitna



Ranger Power
Midnight Solar
120 MW
Near Point MacKenzie

Progress This Quarter: Studies Performed

✓ Interconnection Studies (technical feasibility)

- ✓ LMS Wind Interconnection: **Completed**
 - ✓ Steady-state and dynamic stability assessed at 122 MW
 - ✓ Two transmission lines needed to avoid largest contingency
 - ✓ Ring bus at LMS substation needed
 - ✓ Beluga to Pt MacKenzie line has sufficient capacity
 - ✓ Transfer limits of south and north intertie are impacted
- ✓ Midnight Solar Interconnection: **Completed**
 - ✓ Similar detail to LMS
- Wind + Solar Interconnection: **Expected mid-July**

✓ Meteorological Stations


- ✓ Lidar installed at LMS in June (Tower in Oct. '22)
- ✓ Solar met station installed in June

✓ Natural Gas On-Site Storage FEED Study **Completed**

- ✓ CNG is selected technology
- ✓ Gas storage at Sullivan or SPP possible
- ✓ Capacities studied: Enough to run 50 MW or 100 MW turbines; Storage volume for 6 to 24 hours
- Regulation Study
 - Work in progress, Complete by Aug. 31
- Wind Forecasting
 - ✓ Three forecast services established
 - Ongoing testing
- Integration Study (economic feasibility)
 - ✓ Base model prepared
 - ✓ Initial regulation process provided June 26
 - Scenario modeling by Sep. 29

Regulation of Intermittent Resources is Critical - Wind Forecasting Example

Fire Island Wind Forecasting Performance



Focus Area 1: RFP Next Steps for Renewable Energy

Next Steps

- Complete interconnection studies - July 14, 2023
 - Finalize regulation study and ramp rate requirements - August 31, 2023
 - Integration studies - September 2023
-
- If feasible and cost-effective, negotiate power purchase agreements – October - December 2023
 - Board action on PPA - January 2024
 - Submit agreements to Regulatory Commission of Alaska - February 2024
 - Permitting, purchasing, site preparation, construction - 2024 to 2025
 - Project commissioning and operation - 2025 to 2026



2. Develop Known Renewable Projects: Continue to pursue potential renewable energy projects

Focus Area 2

- Develop Known Renewable Projects

Focus Area 2:

DEVELOP KNOWN RENEWABLE PROJECTS

COMPLETED

- Two AWWU PRV to hydro, 28 kW and 45 kW
- Heat Pump Program
Initiated Feb. 1, 2023

ACTIVE EVALUATION

- Community solar
- Solar on building C
- Two hydro projects
- CNG storage
- Railbelt wind studies
- Two tidal projects
- MOA waste to energy

CONCEPTS

- PRV to hydro #3
- Community Heat Pump
- Refurbish wind
- H2 or solar at Beluga
- Solar at SPP
- Landfill methane
- Pt. Mac Sub solar
- Others under NDA

STOPPED

- Five+ solar projects at distribution system scale

See Appendix B for additional detail.

Focus Area 2: Community Solar Location

- Chugach owned Retherford Substation Property
- 800 E 94th near Old Seward Hwy
- 13.6 acres total
- 500 kW solar
- Little shading
- Interconnect to substation (35kV) or feeder on Old Seward (15kV)



Focus Area 2: Community Solar Update

Coffman Engineering contracted for Front End Engineering and Design

- ✓ Conceptual array design
- ✓ Site design and permitting
 - Geotechnical engineering (Shannon & Wilson)
 - Site survey (Farpoint Land Services)
 - Permitting (Solstice Alaska Consulting)
- Electrical Interconnection Design (7/14)
- Economic Analysis (7/21)
 - Chugach Evaluation of Results
- RFP development for PV Installation (8/11)

Economic evaluation to be completed in September.





3. Create Policy Changes: Pursue regulation and legislative changes that remove regulatory barriers to the deployment of renewable generation

Focus Area 3

➤ Create Policy Changes

Policy Initiatives

- Chugach and Railbelt utilities are working on recommendations for legislation for renewables and clean energy.
- Chugach is prepared to work with a legislative committee or participate in hearings ahead of the 2024 legislative session.
- Chugach is researching legislative bills and industry best practices involving net metering and community solar.

Presentation Take-Away Messages

1. Two big renewable projects will end study phase in September; if feasible, PPA negotiations in Q4
2. Regulating variable sources is critical
3. Community solar economic evaluation in September
4. Many other projects and policies are in development



Questions?



Appendix A

RFP and Study Process Details

RFP Key Process Steps

- 1 • RFP written, issued, distributed widely
 - 2 • Pre-proposal videoconference
 - 3 • Proposal deadline
 - 3 • Form review team:
 - 3 • Chugach economic & technical 4-stage review
 - 3 • Economic screening and notification of proposers
 - 3 • Technical scoring and additional questions for leading proposers
 - 4 • Decision and notification
 - 5 • Develop interconnection study scope, schedule, budget
 - 5 • Develop integration study scope, schedule, budget
 - 5 • Invitation to enter study agreement, delivery of study agreement
 - 6 • Acceptance of study agreement & pre-payment
 - 6 • Study kick-off meetings
 - 7&8 • Data gathering, model inputs, site control
- Sep. 2021
 - Nov. 2021
 - Dec. 17, 2021
 - Dec. 2021
 - Jan. 2 to Feb. 22, 2022
 - Feb. 22, 2022
 - Mar. to Apr. 12, 2022
 - Mar. 25, 2022
 - Apr. 2022
 - Apr. 2022
 - May 18, 2022
 - Sep. 16, 2022 & Nov. 7, 2022
 - Oct. 2022 & Nov. 2022
 - Oct. 2022 to May 2023

Interconnection Study Timeline Examples

- Proposer providing data, modeling, one-line development, PSS/E model development - Oct. 2022 to May 2023
- Scoping & methodology decisions - Oct. 2022
- Railbelt PSS/E model updating - Oct. 2022
- Base case transfer limits, contingency review - Nov. 2022
- Initial modeling new facilities, begin dynamic modeling - Dec. 2022
- Beluga transfer limit - Jan. 2023
- PSCAD modeling, EMT modeling - Feb. 2023
- Modeling and modeling reviews - Apr. 2023
- Multiple interconnection configurations, report writing - May 2023
- Reporting, Chugach review, finalization - Jun. 2023

Appendix B

Focus Area 2 Project Updates

Focus Area 2: Projects Completed

Project	Capacity & Type	Status
AWWU Energy Recovery 1	45 kW Hydro	Completed, operational
AWWU Energy Recovery 2	28 kW Hydro	Completed, operational
Heat Pump Program **	N/A Geo/Air	Feasibility study completed; Heat Pump Incentive Program designed in 2022, implemented 2023.

** Chugach-led initiative * Chugach-involved initiative Others are third-party initiatives

Focus Area 2: Projects Under Active Evaluation 1

Project	Capacity & Type	Status
Community Solar **	500 kW Solar	Chugach hired Coffman Engineers to conduct FEED study to examine the feasibility of locating community solar at Retherford substation near 94 th and Old Seward.
Solar on Building C Expansion **	170 kW Solar	Preliminary design complete, out to bid.
Dixon Diversion *	~40% more hydro energy from Bradley	Chugach awarded \$1M grant from Alaska Renewable Energy Fund on behalf of BPMC; economic feasibility currently under study.
Utility scale hydro **	Hydro	Chugach installed stream gauging to measure water flows. Applied for Renewable Energy Fund Round 15: recommended but not funded.
Natural Gas Storage for regulating renewables **	50-100 MW Storage (for 6-24 hours)	FEED study conducted. Results being considered in economic evaluation of alternatives.
Railbelt wind study *	N/A	Coordinated Railbelt utility study of best possible wind locations and meterological tower installation

Excludes projects from RFP process

** Chugach-led initiative * Chugach-involved initiative Others are third-party initiatives

Focus Area 2: Projects Under Active Evaluation 2

Project	Capacity & Type	Status
Turnagain Arm Tidal	1 MW Tidal	Chugach is supporting all tidal energy development in Cook Inlet and will sign a letter of support for the Turnagain Arm Tidal Electricity Generation project's DOE funding application.
Hilcorp Tidal	TBD Tidal	Hilcorp, Chugach and ACEP examining options; Hilcorp expected to make idle platforms available
Anchorage Waste to Energy Project	20-30 MW Biomass	After project dormancy, a project proponent is actively promoting the project again, met with Chugach in June 2023.

Excludes projects from RFP process

** Chugach-led initiative * Chugach-involved initiative Others are third-party initiatives

Focus Area 2: Concepts Under Consideration

Project	Capacity & Type	Status
AWWU Energy Recovery 3	250 kW Hydro	AWWU awaiting results of prior projects
Seward Ground Source Heat Pump	N/A Geothermal	City seeking other funding sources
AVTEC Wind	100 kW Wind	Recommissioning and commercial arrangement needed
Hydrogen or Solar at Beluga **	TBD	Examined the potential to install solar to replace Unit 7, and the possibility of using unscheduled renewables to produce hydrogen to burn at Beluga
Solar on SPP **	100 kW Solar	Chugach hiring decarbonization contractors then implementing this project in order of priority/availability
Landfill Excess Methane *	Unknown	New concept to consider
Point MacKenzie Substation Solar	5 MW	Adjacent landowner pursuing options to develop solar and interconnect at transmission substation. Very expensive due to high voltage interconnection.
Other options under NDA	>100 MW	

** Chugach-led initiative * Chugach-involved initiative Others are third-party initiatives

Focus Area 2: Projects Stopped or Paused

Project	Capacity & Type	Status
Renewable IPP	6 MW Solar	Multiple locations investigated for distribution-connected solar. IPP ended projects due to poor project economics from high land values and/or citing permitting challenges.
JBER Solar	4.5 MW Solar	JBER paused the project in 2021
3 rd Avenue Solar	50 kW Solar	No known activity by organizer
Solar/EV Charging Demo	20 kW Solar	Third-party decided not to pursue the project
Commercial/Industrial Solar	200 kW Solar (est.)	Third-party found the land unsuitable for solar

** Chugach-led initiative * Chugach-involved initiative Others are third-party initiatives